HASSAN DIVISION.

Dated 3rd October 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 6th November 1918, for constructing an additional block in the compound of the Old High School at Hassan. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an additional block in the compound of Old High School at Hassan," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of the contents of constructing an additional block in front of lower building attached Old High School at Hassan.

Items of work	Per	Quantity
Earthwork excavation and filling in basement	C. yd.	103
Concrete with lime mortar	C. ft.	952
Burnt stone in lime mortar	"	2,558
Burnt brick in clay superstructure	"	3,947
Plastering with clay	Sq.	98·39
Whitewashing, 2 coats	"	63·79
Colour washing	"	36·28
Burnt brick in lime mortar, (arch work)	C. ft.	49
Burnt stone slabs, 6" thick, (dressed)	S. ft.	825
Teakwood pillars with base and capitals	No.	8
Burnt brick in mortar superstructure	C. ft.	677
Teakwood panelled door with hinges, bolts, etc., complete	S. ft.	33
Teakwood panelled window with glazed shutters inside. and iron bars, etc., complete	"	315
Teakwood glazed swinging ventilator with cross iron bars, etc., complete	"	81
Teawood circular ventilators, glazed	"	12
Teakwood panelled almirahs with cross planks, padlocks, etc , complete	"	95
Teakwood work wrought and put up with wood oiling, etc., complete	C. ft.	216·50
Chunam borders	R. ft.	120
Teakwood finials	No.	6
Teakwood pendants	"	20
Teakwood ornamental weather boards.	"	2
Flooring with Cuddappah slabs. over 3" concrete and cement pointing	Sq.	20·22
Roofing with 1st class Mangalore tiles on teak reepers	"	36·91
Ridge tiles set in mortar	R. ft.	152
Silicate painting	Sq.	24·37
Cement pointing to basement	"	4·70
Teakwood planks for valleys	S. ft.	296
Iron clamps for doors and windows	No.	128
Cutting trees and clearing and levelling site, with tarring, etc.	L. S.	Rupees.
Teakwood trusses clear span, 16' including bolts, etc., complete	Each	6
Zinc sheets for valleys	S. ft	296
Teakwood eave board	R. ft.	358

C. T. NARASIMHA IYENGAR,
Assistant Engineer in charge.